Extending and improving the Devaraja Market at Mysore. Estimate for the cost of constructing the central block on the northern side and the block of four shops to its west.

Serial No.	Description of work	Per	Approximate estimate		Remarks
			Ground floor	First floor	
1	Burnt brick in chunam, superstructure	Cubic feet	12,091	7,557	
2	Arch work, burnt brick in mortar	Do	444	231	
3	Burnt stone slabs 6" thick two lines dressed and fixed.	Square feet	1,036	390	
4	Plastering with chunam mortar	Do	213·89	102·23	
5	White and colour washing	Do	213·89	102·23	
6	Roofing with jack arch terrace over steel joists including laying of two courses of flat tiles complete.	Do	18·00	23·51	
7	Roofing with pukka terrace complete with flat tiles, etc.	Do	6.00	0·96	
8	Flooring with Cuddaph slabs over 3" concrete bed and cement pointing, etc., complete	Do	30·28		
9	Cuddaph slabs underneath the steel joists to serve as bearing slabs.	Do	4·64	2·24	
10	Teakwood work wrought and put up	Cubic feet	272·84	7·00	
11	Cut stone bases nicely dressed and fixed	Each	5		
12	Teakwood doors with ordinary panelled folding 1½" thick shutters including bolts, hinges, etc., complete.	Square feet	1,104	256	
13	Teakwood ventilators with glazed shutters including brass rings, ropes, etc., complete.	Do	128		
14	Chocolate painting to doors and ventilators	Do	22·93	9·76	
15	Cornice 9" projection complete	Rft.	125		
16	Cornice 4½" projection complete	Do	153		
17	Dental cornice big	Do	240		
18	Ornamental perforated parapet wall of verandha 2' high.	Do	68	307	(In first floor 3' high)
19	Ornamental cave board 10" x 1" including fixing and painting.	Do	66		
20	Masonry finials big	Each	10		
21	,, small	Do	8	12	
22	Ornamental work for pedestals	Do	4		
23	Ornamental work for big pediment	Do	2		
24	Roofing with jack arch terrace over steel joists including laying, etc., complete but without flat tiles.	Square	23·23		
25	Arch work plisted in cut stone, etc., complete	Cubic feet	136		
26	Cuddaph slabs lovey with brackets	Rft.	60	42	
27	Circular fan lights including teakwood frame, etc., complete.	Square feet	25		
28	Cut stone pillars with base and capitals complete (12¼' x 8" x 8".)	Each	8		
29	,, (7' x 6" x 6")	Do	1	8	
30	,, (6' x 6" x 6")	Do		8	
31	Cut stone pendents for central arches	Do	4		
32	Cut stone brackets finely dressed and fixed	Do		16	
33	Flooring with Mangalore tiles on chunam bed and cement pointing complete.	Square		21·00	
34	Teak wood windows with panelled shutters outside and glazed shutters inside including iron bars, etc., complete.	Square feet		232	
35	Teak wood railings 2 to 2½' high	Rft.		24	
36	Ornamental work including cresting to balcony to windows including small finials, etc. the niches in pilasters, etc., complete as per plan and in balcony also.	Each	4	6	
		Do	8	2	
37	Finishing above arch work front and rear	Do	4		
38	Spandrils a				

C. SRIKANTESWARA AIYAR,
President.

CHITALDRUG DISTRICT.

Notification dated 6th March 1924.

Under the authority vested in the Deputy Commissioner by Notification No. 539—L. B. 18-21-1, dated 26th July 1921, and with the sanction of Government conveyed in their Order No. L. 6283—L. B. 119-22-15, dated 9th February 1924, the Assistant Commissioners in charge of Davangere and Chitaldrug Sub-Divisions are empowered to exercise the powers of the Deputy Commissioner defined in Section 32 of the Mysore Local Boards and Village Panchayets Regulation of 1918 over the Village Panchayets within their respective jurisdictions.

R. NANASWAMI RAO,
Deputy Commissioner.